

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 45 N. EX R. 29 W.	M 7 & M 8	
2. PROPERTY CONTROLLING IN SECTION	T. _____ S. _____ R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 31 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M 7: White Birch post (not found)
W. Birch 6 N68E 33 " "
W. Birch 12 S72W 33 " "
Corner M 8: White Birch post (not found)
Y. Pine 18 S67W 51 " "
Y. Pine 18 N42E 30 " "

No subsequent monuments found at either corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M7: Re-established by proportionate measurement on line between an original sec. corner 80.044 ch. S and an original 1/4 corner 40.022 ch. N.
Corner M8: Re-established by proportionate measurement on line between an original sec. corner 40.022 ch. S and an original 1/4 corner 80.044 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M 7: 1" I.D. x 36" iron pipe with 4" aluminum cap, set at an angle with punch mark over point because of a large boulder in ground at the corner point.
Red Oak 6 N77°W 7.4 ft. "S13, NBT"
Red Oak 6 S29°W 51.1 ft. "S24, NBT"
Red Maple 7 N32°E 12.9 ft. "S18, NBT"
W. Birch 12 S33°E 23.7 ft. "S19, NBT"
Corner M 8: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Red Pine 6 N 31°W 5.3 ft. "1/4S, NBT"
Red Pine 6 S19°E 87.6 ft. "1/4S, NBT"
J. Pine 13 S24°W 69.0 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
APPROVED AND SIGNED BY Arthur O. Enger DATE August 7, 1973
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581