

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 29. W

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 27, 28, 33, 34

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" Red Oak (S 33 NBT) S 68° W 46 1/2 Links

8" Red Oak (S 28 NBT) N 46° W 60 Links

9" Red Oak (S 34 NBT) S 10° W 44 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by Double Proportionate distance from Section corners 1 mile in all four directions. No evidence of original corner. Corner lies on hillside facing SW. Squared and scribed 4" Soft Maple at corner.

Corner was placed and witnessed May 20, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 8/11/60