

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 29W. . .

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER ----- 1/4 cor. for secs: 26-27 -----

DESCRIPTION OF CORNER MONUMENT ----- 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER ----- 15" R. Pine (1/4s NBT) S76° E 63 1/2 Lks. -----

----- 14" R. Pine (1/4s NBT) N41° W 133 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced from probable B.T. Y. Pine stp. bottom bearing S44°E 44 Lks.
Position fits with sec. cor. to north. Found W. Pine stp. (probable
line tree) 2.11 chs. south of cor. Cor. placed and wit. 4/20/59 with
C. Schooley, D.F.

SURVEYORS SEAL

Billy D. Buckler
SIGNED ----- Billy D. Buckler ----- DATE 8/6/59 -----
REGISTERED LAND SURVEYOR