

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 29 W..

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 13, 14, 23, 24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" Aspen ----- N 46° E ----- 22 links to notch.

7" Soft Maple ----- S 21° E ----- 35 links to notch.

6" Soft Maple ----- S 42° W ----- 46 links to notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one White Pine B.T. in place, burned, notch and over growth very plain.

Distance north to 1/4 Corner good; south to swamp edge good.

Corner found by Forestry Division survey crew while making a partial re-survey of this area.

Old squared White Pine stub 12 links West of corner.

Corner placed and witnessed August 13, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler .. DATE 8/17/56  
REGISTERED LAND SURVEYOR