

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 29 N.

Marquette

COUNTY

DESCRIPTION OF CORNER ~~Sec. Cor. common to Secs. 28, 29, 32, 33.~~

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap.

WITNESSES TO CORNER 12" Red Pine S 32° E 59 Links to Notch.

10" Red Oak S 75° W 25 1/2 Links "

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Sec. Cor from two original W. Pine R.F.s, badly burned. Notch and overgrowth very plain on both stumps. Traces of Stake in soil.

Corner found by Forestry Division Survey Crew while making a Partial Re-Survey of this Twp.

Corner placed and witnessed Sept. 21, 1956.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 9/22/56