

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 29 W. . .

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 25, 26, 35, 36

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" Red Pine S 38° W 94 links

8" Jack Pine N 12° E 53 links

13" Jack Pine S 37° E 130 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from remains of two White Pine stump bottoms in proper position.

Traces of stake in soil. Distance checks very good to swamp edge East and South to 1/4 Corner.

Several old blazes along line East of this corner.

Corner found by Forestry Division Survey Crew while making a re-tracement survey of this township.

Corner placed and witnessed August 21, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/4/56
REGISTERED LAND SURVEYOR