

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 29 West

Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner bet. Secs. 22-23

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 7" Red Oak S 76° W 41 Links

marked (1/4 S - NBT)

6" Red Oak N 25° E 27 1/2 Links

marked (1/4 S - NBT)

Distance measured in Links from Center of Brass Cap to NBT Notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaced 1/4 Cor. from probable B.T.s. a W. Pine Stump bearing S 51° W 40 Lks. and a Y. Pine Stp. bottom bearing N 43° E 57 Lks. No identifying marks. Position fits with Corners 1/2 mile North and South, being 43 Lks. East of a straight line bet. Sec. Cors. Checked Position of small pond 4.00 chs. to North which lies about 1 chain West of Line.

Corner placed and witnessed November 7, 1958.

SURVEYORS SEAL

Billy D. Buckler

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 11/10/58