

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 NR. 29 W

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 26, 27, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 24" Red Pine (S 34 NBT) S 80° W 84 Links

7" Red Oak (S 35 NBT) S 10° E 103 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by double proportionate measure from 1/4 corner, 1/2 mile north; Section corner, 1 mile east; Section corner 1 mile south; and Section corner 2 miles west. No evidence of original corner.

Corner was placed and witnessed August 13, 1959 with R. Hinds, Norway.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 4/27/60
REGISTERED LAND SURVEYOR
Billy D. Buckler