

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45. NR. 29. W

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 11, 12, 13, 14 ..

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 13" Red Pine (S 13 NBT) S 70° E 76 Links

15" Red Pine (S 14 NBT) S 71° W 25 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from two probable BT's. W. Pine stump bearing S 74° E 35 Links and W. Pine Stump S 80° W 60 Links. Position checks with Corners north, south, and west. Corner lies on south edge of pond and marsh. As indicated in original field notes.

Corner was placed and witnessed July 29, 1959 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 4/27/60
REGISTERED LAND SURVEYOR
Billy D. Buckler