

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> <sup>N.</sup> <del>XX</del> , R. <u>29</u> <sup>SW</sup> <del>SW</del> <sup>V.</sup>	K8
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>45</u> <sup>N.</sup> <del>XX</del> , R. <u>29</u> <sup>SW</sup> <del>SW</del> <sup>V.</sup>	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> _____, R. _____ <sup>E.</sup> _____ <sup>W.</sup>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner K8:** Spruce post (not found)  
           S. Pine 6 N28W 10       " "  
           Spruce 10 S26E 10       " "  
           Found a 3" x 3" x 5' squared wood post and a steel fence post N56°E  
           8.7 ft. set by unknown party for an approximate corner.

**Corner 3:** Not set in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner K8:** Re-established corner on October 26, 1971 on line between section corners 39.988 ch. to N and to S. Corner falls about 50 links N of swamp edge as reported in original field notes.

**Corner 3:** Established October 26, 1971 on line between 1/4 corner 19.994 ch. S and section corner 19.994 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for both corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner K8:** Cedar 8 S15°E (mag.) 20.6 ft. "1/4S, NBT"  
                                   Cedar 15 S36°W (mag.) 32.6 ft. "1/4S, NBT"

**Witnesses for Corner 3:** B. Spruce 6 N53°E (mag.) 6.6 ft. "1/16S, BT"  
                                   Tamarack 5 N77°W (mag.) 32.4 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE November 30, 1972  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger** (SEAL)

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581