

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
2. PROPERTY CONTROLLING IN SECTION <u>23</u> T. <u>45</u> N. _____ S. _____ R. <u>29</u> E. _____ W. _____		8 & 10
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 2, 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 8: Not established in original survey nor subsequently, apparently.

Corner 10: Not established in original survey. Found a 2" squared spruce post at corner, indicating prior establishment.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 8: Established on line between Center 1/4 corner 19.873 ch. E and $\frac{1}{4}$ corner 19.873 ch. W.

Corner 10: Established on line between Sec. Corner 20.088 ch. S and 1/4 corner 20.088 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner 8: Cedar 9 N50°W (mag.) 4.0 ft. "1/16S, BT"
Cedar 7 S48°E (mag.) 12.0 ft. "1/16S, BT"

Witnesses for Corner 10: B. Spruce 6 S10°E (mag.) 7.8 ft. "1/16S, BT"
J. Pine 8 N22°W (mag.) 32.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson CHIEF OF SURVEY PARTY DATE December 27, 1972

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE December 27, 1972 (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581