

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 45 N. R. 29 <del>XX</del> W.	J8
2. PROPERTY CONTROLLING IN SECTION 23.....	T. 45 N. R. 29 <del>XX</del> W.	11 & 12
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **see below** 19\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corners J8, 11, & 12: Not established in original survey and by approximation only, subsequently. At Corner J8, found a 2" squared post S62°W 13.0 ft.; at Corner 11, found a 2" squared post S51°E 6.8 ft.; at Corner 12, found a 1½" iron pipe S54°E 39.8 ft.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner J8: Corner established 11/2/71 at intersection of quarter section lines.**  
**Corner 11: Established 11/3/71 at intersection of quarter-quarter section lines.**  
**Corner 12: Established 11/3/71 on line between Center 1/4 cor. 19.988 ch. N and S 1/4 corner 19.988 ch. S.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**

**Witnesses for Corner J8: Cedar 12 S50°W (mag.) 19.7 ft. "1/4S, BT"**  
**Cedar 10 S62½°E (mag.) 16.8 ft. "1/4S, BT"**  
**Cedar 8 N19°E (mag.) 10.5 ft. "1/4S, BT"**

**Witnesses for Corner 11: R. Maple 8 N76°W (mag.) 23.8 ft. "1/16S, BT"**  
**R. Maple 6 S34°W (mag.) 12.0 ft. "1/16S, BT"**

**Witnesses for Corner 12: W. Pine 14 N16°E (mag.) 51.3 ft. "1/16S, BT"**  
**B. Spruce 8 S23°W (mag.) 30.3 ft. "1/16S, BT"**  
**W. Pine 12 S37°E (mag.) 34.8 ft. "1/16S, BT"**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY **Arthur O. Enger** DATE **December 29, 1972**  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. **13581**