

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 ^{N.} XX R. 29 ^{EX} W.	J 9
2. PROPERTY CONTROLLING IN SECTION 23	T. 45 ^{N.} XX R. 29 ^{EX} W.	15 & 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} XX R. ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on November 3 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J9: W. Pine 14 quarter section corner (not found)
 No witnesses
 Found a 2" squared post N38°W 27.5 ft. and an 8" balsam with 4 sided blazes S51°W 16.5 ft. for approx. corners.

Corners 15 & 16: Not established in original survey and by approximation only, subsequently. At Corner 15, found a 3" cedar post N68°E 17.8 ft. and at Corner 16 found a steel fence post N12½°W 38.0 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J9: Re-established on line between Section Corners 39.902 ch. to E and to W.
Corner 15: Established on line between Sec. Cor. 19.951 ch. W and 1/4 corner 19.953 ch. E.
Corner 16: Established on line between Sec. Cor. 19.951 ch. E and 1/4 Cor. 19.953 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner J9: Cedar 8 S29°E (mag.) 32.8 ft. "1/4S, NBT"
 W. Pine 10 N47°W(mag.) 39.4 ft. "1/4S, NBT"
Witnesses for Corner 15: Cedar 5 S82°W (mag.) 9.5 ft. "1/16S, BT"
 Cedar 4 N33°E (mag.) 10.8 ft. "1/16S, BT"
Witnesses for Corner 16: R. Pine 12 N78°E (mag.) 24.7 ft. "1/16S, BT"
 R. Pine 8 S40°E (mag.) 33.0 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Carl R. Johnson CHIEF OF SURVEY DEPT. Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE January 2, 1973

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581