

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MARQUETTE

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 29 <del>XX</del> W.	M4 & M5
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 30 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner M4: Yellow birch post	(Not found. No subsequent monuments found)
W. Birch 5 S44½E 28	( " " " " accessory " )
W. Birch 8 N85W 19	( " " " " " " )
Corner M5: Maple post	(Not found)
Maple 20 S82E 27	" "
W. Pine 10 N56W 13	(Found)
W. Pine 20 N63E 20	(Found)

Found a rotted off squared pine post at a fence corner about 2.70 ch. N of corner reported herein. CCI location tag nearby.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner M4: Re-established proportionately on line between original line tree stumps 13.627 ch. S and 11.313 ch. N. LT to S identified by its correct relationship to a boulder reported in original field notes as being 2 lks. E; LT to N located by calculating its probable position and locating the only stump in vicinity that agreed with that position. An apparent error in original triangulation across a pond to N results in the N½ mile between Sec. 7 & 12 being 39.602 ch. long, while the S½ mile is 40.030 ch. long.

Corner M5: Re-monumented from burned stumps of two original BT's, identified by proportioning the line between an original 1/4 corner S of corner and an original line tree N of corner. The corner point witnessed by the two stumps falls .035 ch. N and .008 ch. W of the proportionate position, so accepted the stumps as the original BT's, though no identifying marks remained.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner M-4: 1" I.D. x 36" iron pipe with 4" aluminum cap.	
R. Oak 13 S11°W (mag.) 25.0 ft. "1/4S, NBT"	
R. Oak 9 N21°E (mag.) 16.0 ft. "1/4S, NBT"	
Corner M-5: 1" I.D. x 36" iron pipe with 4" aluminum cap.	
R. Pine 6 S 7°E (mag.) 49.6 ft. "S18, NBT"	
R. Oak 12 S26½°W (mag.) 29.2 ft. "S13, NBT"	
R. Oak 8 N83½°W (mag.) 61.0 ft. "S12, NBT"	

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE August 0, 1973

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

