

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

WARGUETTE

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---|---------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 45 N. R. 29 XX W. | K9 & K10 |
| 2. PROPERTY CONTROL- ING IN SECTION 26 | T. 45 N. R. 29 XX W. | #7 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. S. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 14 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K9: Cedar post (Not found)
 Spruce 6 N35W 23 { " " No subsequent accessory found.)
 Spruce 8 S38E 22 { " " }
 Found a 2"x2"x30" sq. cedar post N64°E 10 lks.; a 2"x2"x56" sq. spruce post with a telephone company steel post cable route marker alongside it; and a very old squared-up 6" cedar, with a very old cruiser's tree about 15 lks. SE of it, N10°E 46 lks.; from corner reported herein.

Corner K10: Cedar post (Not found. No subsequent monuments found.)
 Spruce 9 N7E 28 (" " " " accessory "
 Spruce 9 N8W 15 (" " " " " "

Corner 7: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K9: As the numerous points found being used for this corner seem to indicate uncertainty as to true corner location, it was re-established by double proportionate measurement between original corners 1 mile N, 1 mile S, 1 mile E, and 1 mile W.

Corner K10: Re-established on line between sec. corners 39.990 ch. to N and to S.

Corner 7: Established on line between sec. cor. 19.995 ch. N and 1/4 cor. 19.995 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K9: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Cedar 4 S65°W (mag.) 3.8 ft. "S26, NBT"
 Cedar 7 S50°E (mag.) 12.9 ft. "S25, NBT"
 Tamarack 5 N82°E (mag.) 18.5 ft. "S24, NBT"

Corner K10: 4"x4"x5½' squared cedar post, scribed "1/4, 25, 26"
 Cedar 8 N10°W (mag.) 4.5 ft. "1/4S, NBT"
 Cedar 6 S60°W (mag.) 12.6 ft. "1/4S, NBT"

Corner 7: 4"x4"x5½' squared cedar post, scribed "1/16, 25, 26"
 J. Pine 12 N36°W (mag.) 3.0 ft. "1/16S, BT"
 R. Pine 15 S63°W (mag.) 23.5 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 7, 1973

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

