

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Marquette

(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>45N</u> R <u>29W</u>	<u>K12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Dec 12 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (K12) Quarter corner common to Sections 35-36. 1956 - Remonumented by Billy D. Buckler RLS: Replaced 1/4 corner from one W.Pine (probable) B.T., poor condition. Distance to swamp edge checks. Old post set by unknown persons. Traces of stake in soil. Set 1" pipe with 4" brass cap. 16" R.Pine N67E 125 links, 9" J.Pine S30W 98 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K12) Recovered the 1956 monument, leaning. Plumbed the monument to be in accord with the record witnesses, both found in good condition with overgrown blazes as follows: 25" R.Pine N70E 82.5', 13" J.Pine S31W 64.7'. Left the monument in place and made two new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K12) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in the following:
 13" W.Pine S73E 14.65' "1/4S NBT"
 13" Spruce S03E 31.23' do
 Sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tags.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/19/02