

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Marquette

(County)

Located in:

Corner Code #

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>45N</u> R <u>29W</u>                 | <u>J8</u>   |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>23</u> T <u>45N</u> R <u>29W</u>     | <u>8</u>    |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Oct 21 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J8) Center of Section 23. 1971: Established by A.O.Enger, RLS: Corner established 11/2/71 at intersection of quarter section lines. Set 1"IDx36" iron pipe with 4" aluminum cap. Witnesses: Cedar 12 S50W 19.7', Cedar 10 S62 1/2E 16.8', Cedar 8 N19E 10.5' (8-Sec. 23) West 1/16 corner, Section 23. 1971: Established by A.O.Enger, RLS: Established on line between Center 1/4 corner 19.873 ch. E and N1/4 corner 19.873 ch. W. Set 1"IDx36" iron pipe with 4" aluminum cap. Cedar 9 N50W 4.0', Cedar 7 S48E 12.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J8) Recovered the 1971 monument slightly disturbed by a falling tree. Plumbed the monument to be in accord with the 1971 witnesses, the cedar SE being dead, the cedar NE in good condition and found with scribing visible, and the cedar SW, in good condition found with overgrown blazes. Distance west to 1/4 checks fairly well with Enger's measure (2.7' longer than record).  
 (8-Sec. 23) Recovered the 1971 monument in good condition and at record bearing and distance from the 1971 BTs, both in good condition. Cut the 1971 BTs to facilitate GPS observations at this corner. Found this monument to be 0.77' E and 0.6' S of the position of record. Accepted the monument as the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J8) Found 1"ID iron pipe with 4" aluminum MDNR cap. Blazed and scribed:  
 7" Cedar S76E 26.0' "1/4S NBT"  
 11" Cedar N50W 19.2' do  
 9" Cedar N23E 10.5' scribing vis. \*  
 12" Cedar S54W 19.8' overgrown blz \*  
 Bearings are magnetic. Distances to notch in lower blaze. \* denotes found 1971 BT.

(8) Found 1"ID I.pipe with 4" alum. MDNR cap. Blazed and scribed:  
 6" Cedar N15E 12.3' "1/16S BT"  
 6" Cedar S88E 21.3' do  
 8" Cedar S08E 23.8' do  
 5" B.Spruce N76W 12.0' do  
 Sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/23/02

For the Michigan Department of Natural Resources - Office of Property Management