

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Marquette

(County)

Located in: Corner Code #

1. Public Land Survey	T	45N	R	29W	17
	T	45N	R	29W	18
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Oct 22 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3					2		1	
3												
4	7	8	9	10					11		12	
5												
6	18	17	16	15					14		13	
7												
8	19	20	21	22					23		24	
9												
10	30	29	28	27					26		25	
11												
12	31	32	33	34					35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- (I7) Corner common to Sections 14-15-22-23. 1984: Remonumented By James Minard, RLS 30091 (Liber 4 of LCRC, Page 410) at position of record described in Liber 2, Page 25. Set capped rebar and wood post. Witnesses: PK nail and tag in the following: 7" Maple S52E 25.46, 6" W.Birch N30E 18.70', 8" W.Birch S25W 53.44'. Spike and tag in 14" Poplar S68W 25.64'.
- (I8) Quarter corner common to Sections 22-23. 1958: Remonumented in the likely original position by Billy D. Buckler, RLS. Set 1" pipe with 4" brass cap. Witnesses: 7" Red Oak S76W 41 links, 6" Red Oak N25E 27.5 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (I7) Found a 1/2" dia. rebar with cap #25836 and #30091, in good condition, and at record bearing and distance from the 1984 accessories, now all dead and recovered as follows: 7" Maple SE a rotted stump, 6" W.Birch NE a 4' tall stub, 14" Poplar SW dead and down, 8" W.Birch SW a 20' tall snag. Found a wood post N35W 0.6' and metal fence post 4.5' tall, S73W 0.2' from the monument. Accepted the monument as marking the position of the corner.
- (I8) Recovered the 1958 monument, in good condition, at record bearing and distance from the 1958 NBTs. The R.Oak NE is now a stump. The R.Oak SW is in good condition with blazes overgrown. Left the monument in place and made new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| (I7) Found 1/2" dia rebar with cap #25836 and 30091. Blazed and scribed:<br>5" R.Oak N13E 13.7' "S14 NBT"<br>7" dbl. Maple N37E 17.8' do<br>8" W.Pine S02W 60.2' "S22 NBT"<br>5" Spruce S70W 61.1' do<br>Bearings are magnetic. Distances are to notch in lower blaze. | (I8) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Found nails with tags "30097 ECI" in:<br>9" W.Birch in clump N66E 21.45'<br>5" Maple S69W 21.52'<br>5" Maple in clump N31W 22.72'<br>Distances are to nail with tag.<br>The 1958 NBT:<br>11" R.Oak S83W 27.1' estim. to notch<br>An 8" R.Oak with old blazes and location poster affixed is S46E 9.4' distant. |
|--|--|



Signed by Stephan J. Szyszkoski Date 10/23/02  
 Surveyor's Michigan License No. 33986