

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>29W</u>	<u>12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>45N</u> R <u>29W</u>	<u>7</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	12 Aug 10 2004	
	7 Aug 09 2004	

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I2) Quarter corner common to Sections 2-3. 1958 - Billy D. Buckler, RLS remonumented the corner at record bearing and distance from burned stumps of original BTs: Y.Pine N50E 39 links, and W.Pine S70W 11 links. Set 1" Iron pipe with 4" brass cap. 26" Y.Pine stump N72W 43.5 links, Y.Pine stump N50E 39 links (the original BT, made new markings).

(7-Sec. 2) North 1/16 corner between Sections 1 and 2. Not established in the original survey. The U.S. Plat of this township gives distances 20.00 chains south the 1/4 corner and 20.71 chains north to Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I2) Recovered the 1958 monument, disturbed, the top being bent over and cap missing, with 5/8" rebar found adjacent. The underground portion of the pipe is vertical and appears to be in the original position. The 5/8" rebar was found marking that position. The 1958 NBTs check fairly well: rotting Pine stump with scribing and notch N51E 25.0', Pine stump with scribing and notch N68W 29.0'. Accepted the pipe as a careful and faithful reestablishment of the position of the original corner and replaced it with a new monument, described below. Left the 5/8" rebar adjacent.

(7 - Sec. 2) Established the corner on a straight line between monumented corners K1 1361.43' north and K2 1314.78' south, the distances being proportionate to those shown on the U.S. plat.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 5" Cherry N65E 27.0' "1/4S NBT"
 4" Cherry S20E 54.9' do
 13" J.Pine N14W 40.9' do
 Set nail/tag in Power pole #4529 03R
 60" S51W 83.5'
 5/8" rebar adjacent. Bearings are magnetic. Distances are to nail with tag.

(7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 12" J. Pine N27E 6.1' "1/16S BT"
 8" J.Pine S84E 6.7' do
 10" J.Pine S01E 10.9' do
 9" J.Pine S67W 3.2' do
 Set sq'd J.Pine post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/2/04

For the Michigan Department of Natural Resources, Office of Land and Facilities