

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T <u>45N</u> R <u>29W</u>	<u>C-E-SE 1/64</u>
	S <u>34</u> T <u>45N</u> R <u>29W</u>	<u>14</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/15/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(C-E-SE 1/64 cor. Sec. 34) 1/64 corner being the SE corner of the SW 1/4 of the NE 1/4 of the SE 1/4 of Sec. 34. Not established in the original survey.

(14-Sec. 34) South 1/16 corner between Sections 34-35. 1985 - Established by K.L.Sackett RLS midway and on line between Quarter corner north and Section corner south. Set 1"IDx32" I.pipe with 4" alum. cap. 14" J.Pine N02W 19.1', 5" J.Pine N80E 40.7', 3" J.Pine S01E 14.3'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C-E-SE 1/64 cor.) Established the corner midway and on a straight line between monumented 1/16 corner #13, Section 34 and monumented 1/16 corner #14, Section 34.

(14-Sec. 34) Found the 1985 monument in good condition and at record bearing and distance from the 1985 witness trees J.Pine N02W (measured as N02E) and J.Pine NE, both in good condition with scribing visible. I found the monument to have been set at the record position and accepted same as a careful and faithful establishment of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(1/64) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" J.Pine S75W 25.55' mrkd "1/64S BT"  
 7" J.Pine S47W 18.5' do  
 3" Cherry S16E 8.8' do  
 4" Poplar S65E 17.3' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

(14) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 18" J.Pine N02E 19.8' old marks (1985 BT)  
 7" J.Pine N85E 41.0' do do  
 3" J.Pine S38E 20.55' mrkd "1/16S BT"  
 5" J.Pine N79W 18.9' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 07/27/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities