

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 29W	I13
	T 45N R 29W	I12
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		



I, Stephan J. Szyszkoski, in a field survey on I12 07/15/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2			1
3													
4	7		8		9			10		11			12
5													
6	18		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I13) Corner common to Sections 34-35 T45N-R29W and Sections 2-3 T44N-R29W. 1961 - Reestablished by Billy D. Buckler RLS by proportionate measurement. Set 1" pipe with 4" brass cap. 9" J.Pine N70E 14 links, 10" J.Pine S10E 62 links, 9" J.Pine S45W 103 links. 1994 - Recovered and witnessed by the undersigned: Found 1" pipe with 4" brass cap. Fd J.Pine NE dead, J.Pine SE a stump, J.Pine SW in good condition. 1994 NBTs: 8" J.Pine N53E 35.1', 10" Aspen N30W 44.0'. The 1994 certificate was placed in the Dickinson County record.

(I12) Quarter corner common to Sections 34-35. 1959 - Reestablished by Billy D. Buckler RLS by proportionate measurement between Section corners. Set 1" ID Iron pipe with 4" brass cap. 9" J.Pine N81E 10 links, 8" J.Pine S45E 37 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I13) Found the 1961 monument in good condition. The 1961 NBT J.Pine SW is now dead. The 1994 NBT J.Pine NE is gone. The 1994 NBT Poplar is in good condition with scribing visible. The NBTs were found at record bearing and distance. Left the monument in place and made new witnesses as described below.

(I12) Found the 1959 monument in good condition and at record bearing and distance from the 1959 NBTs. The J.Pine NE is dead and down. The J.Pine SE is a dead standing stub. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I13) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 10" Poplar N29W 44.25' old marks (1994 NBT)
 6" Poplar N26E 45.7' mrkd "S35 NBT"
 3" J.Pine S66E 36.25' "S2 NBT"
 7" J.Pine S33W 43.5' "S3 NBT"
 Treated 4x4 adjacent. Bearings magnetic.

(I12) Fd. 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 4" twin Spruce N57E 18.7' mrkd "1/4S NBT"
 3" Poplar S20W 13.0' do
 16" J.Pine N63W 21.85' do
 4" Cherry N14W 15.85' do
 4x4 treated post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/27/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities