

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 34 T 45N R 29W	PCC 460122
	S 34 T 45N R 29W	PCC 470122
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 470122 07/15/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(PCC 460122) Northwest corner of the South 100.00' of the SW 1/4 of the NE1/4 of the SE1/4 of Section 34.

(PCC 470122) Northeast corner of the South 100.00' of the SW1/4 of the NE1/4 of the SE1/4 of Section 34.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(PCC 460122) Established the corner on the East N-S 1/16 line 100.00' north, as measured on a perpendicular to line 460120-500120, of the 1/16 corner 460120. Straight line distance to 460120 is 100.02'.

(PCC 470122) Established the corner on the E-E 1/64 line and 100.00' north, as measured along a line perpendicular to 460120-500120, of the C-E-SE 1/64 corner, Section 34. Straight line distance to 1/64 corner is 100.02'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(460122) Set 1"IDx32" I.pipe w/4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Spruce N08W 25.9' mrkd "X BT"
 9" J.Pine S12W 15.8' do
 4" Balsam N62W 39.2' do
 5" Balsam N27W 24.2' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(470122) Set 1"IDx32" I.pipe w/4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" J.Pine N10W 11.6' mrkd "X BT"
 2" Cherry N49E 16.65' do
 2" Cherry S85E 19.05' do
 2" Cherry S29W 14.65' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/27/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

