CONS. 4047 REV. 10/60 MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

Francy

LAND CORNER RECORD

T. 45 N.R. 30 W

		Marquette	COUNTY
DESCRIPTION OF CORNER _	Meander Corner on N. si	de Pickerel Lake bet. Sec. 32	& 33
CORNER MONUMENT	32" x 32" x 6" squared	cedar post scribed "32, 33, M	C#
DATE MONUMENT PLACED AN	0 WITHESSED		
WITHESSES TO CORNER	Cedar 8 N19W 361 1ke	. "MC MBT"	
N	Cedar 8 SSAW 51 1ks	. HMC NBTH	
CIRCLE CORNER REGISTERED	AND		

DESCRIPTION IN DETAIL AS TO NOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument was placed from two original tamarack BT's: Tam. 3 N5E 26 which is a fragile 2 ft. high stub with lower blaze and scribe marks "BT" plain; and a Tam. 6 N7OW 41, now a badly rotted stump with no visible marks. Found traces of an old post in the muck at the corner location, believed to be part of original tamarack post. Found an old 3" x 3" x 5½ squared cedar post S83E 3 lks. from true corner, set by unknown surveyor, and old blazes on trees in vicinity.

SURVEYOR'S SEAL

SIGNED ______ DATE 9/4/68____