

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY
T 45N R 30W

DESCRIPTION OF CORNER M.C. on North side of Witch Lake between Sec. 23 & 24

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 9, 1969

WITNESSES TO CORNER..... Red Maple 9 N41°W 39 lks. "MC NBT"



Cedar 11 S48½°E 70½ lks. "MC NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at an old 1" O.D. x 3' long iron pipe which was set prior to 1943 by an unknown surveyor, from the stumps of two original W. Pine bearing trees. Both stumps are still in position and agree with originals in species, absolute and relative size, and bearing and distance from corner. Both are badly deteriorated, but one has axe marks which may be part of original lower blaze. This corner is reported in a survey by the Marquette County Road Commission on April 30, 1943.

The present variation at this corner appears to be about 6°00' East.
Variation at time of original survey was 0°55' East.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/20/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68