

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY


T 45N R 30W

DESCRIPTION OF CORNER Meander corner between Sec. 25 & 26, So. side Witch Lake

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 16, 1969

WITNESSES TO CORNER..... Cedar 9 S80°E 31 lks. "M.C. NBT"



Balsam 4 S36°W 32 lks. "M.C. NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at Northerly terminus of an old fence line from the South at the edge of Witch Lake. The direction of the fence line extended northerly across the lake points almost exactly to an original meander corner on the north side of the lake. Distance across lake to north M.C. computed by triangulation to be 33.395 chains (record: 35.10 chains). Distance south to an iron pipe purporting to be Sec. Cor. 25, 26, 35, & 36 is computed by traverse to be 76.888 chains (record: 77.65 chains). No evidence of original corner or its accessories.

The variation at this corner appears to be about 4°30' East.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/21/69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68