Cons. 4047 REV. 10/60

MICHIGAN DEPARTMENT OF CONSERVATION FORESTRY DIVISION

LAND CORNER RECORD

T. 44-45 N.R. 30W

			Marquette-Dickinson coun	ΤΥ
DESCRIPTION OF CORNER	E 1/16 corner	between 2 & 3		_
CORNER MONUMENT 4" × 4"	x 6' equared	cedar post ser	ribed "B 1/16 S, 1/16 S, 2, 35"	_
DATE MONUMENT PLACED AND	WITHESSED	y 29, 1968		_
WITHESSES TO CORNER	Cedar 7	8891W 161 1kg	. "1/16 8 BT"	
N 2	Cedar 6	530½E 16½ 1ke	. *1/16 S BT*	
CIRCLE CORNER REGISTERED	AND			- -

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established midway on line between the 1/4 corner 20.00 chains west and Sec. Cor. 20.00 chains east, as previously established by proportionate measurement. Corner is in a cedar-spruce swamp.

No evidence that a corner ever was set here, but found very old E & W blases on a tamarack stub a few links SE of post.

SURVEYOR'S SEAL

SIGNED ______ CATCHUR O. Enger DATE 9/4/68