

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette-Dickinson COUNTY


T 44-45N R 30 W

DESCRIPTION OF CORNER 1/4 corner between Sections 4 and 33

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 6, 1968

WITNESSES TO CORNER..... Red Maple 6 North 31 1/2 lks. "1/4S NBT"



Sugar Maple 6 883°W 74 1/2 lks. "1/4S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner established midway on line between Section Corners 40.255 chains to East and West, as previously established by proportionate measurements.

No evidence of original monument or its accessories or of any replacement monument or its accessories. Distance across this section line appears longer than record distance, according to the falling at natural features mentioned in the original field notes.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68