


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY
T 45N R 30W

DESCRIPTION OF CORNER Section Corner 25, 26, 35, and 36
CORNER MONUMENT 1½" O.D. x 36" iron pipe with galvanized pipe cap
DATE MONUMENT PLACED AND WITNESSED May 7, 1969
WITNESSES TO CORNER..... Red Pine 9 N64°W 103½ lks. "S26, NBT"



Sugar Maple 7 S15°W 25½ lks. "S35, NBT"
Aspen 7 N49½°E 34½ lks. "S25, NBT"

AND
All bearings are magnetic

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument recorded as found in place on above date. This monument is identical to several others found within a mile to east and west of M-95, for a distance of about 3 miles to the south. These pipes are believed to have been placed by the Michigan Dept. of State Highways in the mid 1930's, although no information could be uncovered in Highway Dept. files. Two of these corners are known to have been set from original evidence because the evidence is still there, but how the others, including this one, were set is not known. This pipe is 79.49 chains northerly of a similar pipe purporting to be the SE corner of Sec. 35 (record distance is 80.00 chains), but the latter corner does not agree with original record of corners on the town line between T44N and T45N. This pipe is also 110.28 chains southerly of a known original meander corner on the north side of Witch Lake between Sec. 23 and 24 (record distance is 112.75 chains).

In consequence of adjoining property owners having used this pipe for surveys of their property, and despite a lack of positive evidence as to the original corner, this corner is perpetuated as found.

SURVEYOR'S SEAL

SIGNED

Arthur C. Enger
REGISTERED LAND SURVEYOR

DATE

11/28/71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68