

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


Marquette COUNTY
T 45 N R 30 W

DESCRIPTION OF CORNER 1/4 corner between Sections 35 and 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED May 5, 1969

WITNESSES TO CORNER..... W. Pine 12 N12½°E (magnetic) 70 links "1/4S, NBT"



W. Pine 12 S14°E (magnetic) 43 links "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found aspen post for approximate corner S2½°E 27½ links of corner.
Probably set about 1961.

Corner re-established on line between MDNR section corner on south twp.
boundary 39.996 ch. south and a found 1½" iron pipe with galvanized pipe cap
39.996 ch. north. Original field notes call to "descend hill 30 feet" at
5.00 ch. north of this corner was found at 4.85 ch. north of corner.

Variation about 1°50' West.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE August 25, 1971

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68