

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY
T 45N R 30W

DESCRIPTION OF CORNER 1/4 corner between Sections 21 and 22

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 14, 1972

WITNESSES TO CORNER..... Basswood 7 S78°E (mag.) 24.6 ft. "1/4S, NBT"



Basswood 7 N42°E (mag.) 46.2 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by transit and tape traverse on line between original section corners 2609.0 ft. to N and to S. Corner falls on N edge of an E & W woods road and on E edge of a N & S powerline clearing. Found a very old N & S line blaze on a cedar stub about 100 ft. S. Section line measures short of record chainage, but a similar shortage was noted on the E line of Sec. 22.

Variation 2°20' at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor (Copy to Marquette County Road Commission)

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

June 26, 1972