

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY


T 45N R 30W

DESCRIPTION OF CORNER Meander Corner between Sec. 22 & 27 on West Shore of Twin Lake

CORNER MONUMENT 3/4" I.D. iron pipe (length unknown)

DATE MONUMENT PLACED AND WITNESSED February 14, 1972

WITNESSES TO CORNER..... White Pine 12 N75½°W (mag.) 30.7 ft. "MC, BT"



Hemlock 5 S33°W (mag.) 16.8 ft. "MC, BT"

Note: These NBT's presumably made by person  
AND setting the pipe.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

By field measurements, found the above pipe to bear due East 2311.0 feet (35.015 chains) from 1/4 cor. bet. Sec. 22 & 27, compared to record distance of 35.22 chains; and to bear S32°18'W 590.9 feet (8.953 chains) from the M.C. bet. Sec. 22 & 23 on N side of Twin Lake, compared to calculated record bearing and distance of S31°31'W 580.7 feet (8.798 chains). 1/4 cor. bet. Sec. 22 & 27 and M.C. bet. Sec. 22 & 23 are known to be original corners. Difference between original and present measurements is not unreasonable, so accepted pipe as found.

Variation 4°30' East at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE July 17, 1972

Arthur O. Enger

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68