


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY
T 45N R 30W

DESCRIPTION OF CORNER Section Corner 15, 16, 21, and 22
CORNER MONUMENT 2"x36" iron pipe with 2" brass cap (by G.L.O.)
DATE MONUMENT PLACED AND WITNESSED December 13, 1971

WITNESSES TO CORNER..... Sugar Maple 6 N69½°E (mag.) 18.4 ft. "S15, NBT"



Sugar Maple 9 S58¼°E (mag.) 44.1 ft. "S22, NBT"

Sugar Maple 7 N48°W (mag.) 48.4 ft. "S16, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 2"x36" iron pipe with 2" brass identification cap in place as set by Robert W. Livingston, General Land Office Surveyor, in September 1929. Corner had been perpetuated in 1929 from the original BT's in the course of a G.L.O. survey of islands in nearby lakes. I confirmed that the monument is undisturbed from the remains of one of Livingston's 1929 NBT's, a Maple 18 866°00'W 62 links, which I found as a rotted stump with a weathered portion of witness blaze with faint scribe marks visible. No trace of a second NBT. (Refer to G.L.O. transcript No. 6881 on file with Lands Division, Department of Natural Resources, Lansing, Michigan 48926 for complete information.)

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

County Road Commission

SIGNED

Arthur O. Enger

REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE October 30, 1972