

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	T. <u>45</u> N. S., R. <u>30</u> E. W.	<u>7, 9, 9a, & 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

None of these corners established in original survey and I found no evidence that they were established subsequently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 7: Established 3/20/72 on line between Sec. Cor. 1304.6 ft. N and 1/4 corner 1304.6 ft. S.
- Corner 14: Established 4/12/72 proportionately on line between 1/4 cor. 1293.7 ft. N and M.C. 808.6 ft. S.
- Corner 9: Established 3/20/72 on line between calculated Center 1/4 cor. (in lake) 1314.6 ft. W and E 1/4 cor. 1314.6 ft. E.
- Corner 9a: Established 4/12/72 on E shore of lake on E & W 1/4 line 264.5 ft. W'ly of Corner 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all four corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Witnesses for Corner 7: Balsam 5 S77¹/₂°W (mag.) 17.5 ft. "1/16S, BT"
 (Variation 4°50' East) Sugar Maple 6 N40°W (mag.) 12.5 ft. "1/16S, BT"
 Witnesses for Corner 14: W. Birch 8 N44°W (mag.) 17.7 ft. "1/16S, BT"
 (Variation 5°40' East) W. Birch 9 S39°W (mag.) 19.6 ft. "1/16S, BT"
 Witnesses for Corner 9: W. Birch 9 N40°W (mag.) 24.0 ft. "1/16S, BT"
 (Variation 5°05' East) R. Maple 7 N77°E (mag.) 17.5 ft. "1/16S, BT"
 Witnesses for Corner 9a: B. Spruce 6 N24°E (mag.) 9.8 ft. "AMC, BT"
 (Variation same as 9) B. Spruce 6 N80°W (mag.) 11.2 ft. "AMC, BT"
 Note: Distances horizontal. 9a stamped "Aux. M.C., E-W 1/4 line, Section 22"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 27, 1972
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581