

OK.  
B.McD

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Marquette Located In: \_\_\_\_\_ Corner Code #/ #  
(County)

1. Public Land Survey T 46N R 23W C-1, C-2.  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 1/29, 1987, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- C-1. NE section corner of Section 6.
- C-2. East 1/4 corner of Section 6. Wood post. Sugar 11, N75E, 8 Lks.  
DO 12, N75W, 17 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-1. Found squared wood post, not of record but this position fits very well for record mea. to a stream 5.25 chs. east and is reasonably close to record measurement south to the east 1/4 corner and west to the north 1/4 corner of Section 6. I find no reason to dispute the position of this post. Replaced squared post with DNR monument.
- C-2. Set at very old fence corner in west edge of beaver flooding. This is very near the single proportion position between the NE and SE section corners of Section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1. DNR Monument.  
4" balsam, N52W, 7.7'  
4" maple, S4W, 21.05'  
5" maple, S51E, 17.0'  
6" bl.cherry, N75E, 22.4'
- C-2. DNR Monument.  
7" maple, N72W, 89.2'  
6" cedar, S85W, 91.2'  
5" cedar (dead), S12E, 16.2'  
5" cedar (dead), N82E, 16.1'

Signed by \_\_\_\_\_ Date \_\_\_\_\_

Surveyor's Michigan License No. RLS 21558