

OK  
B.McD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code <u>4,7,8,9</u>
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>46N</u> R <u>23W</u> S _____ T _____ R _____	<u>4,7,8,9</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 2/3/87, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 4. NW 1/16 corner of Section 6. (Ctr. of the NW $\frac{1}{4}$ ). No previous record.
- 7. North 1/16 corner on the East section line of Section 6. No previous record.
- 8. W 1/16 on the E&W 1/4 line of Section 6.
- 9. East 1/16 corner on the East & West 1/4 line of Section 6. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 4. Set at the computed center of the NW $\frac{1}{4}$  of Section 6 by closed traverse.
- 7. Set by single proportion to the GLO record between the East  $\frac{1}{4}$  corner and the NE section corner of Section 6.
- 8. Set at the single proportionate position between the West 1/4 corner and the center of Section 6.
- 9. Set MPOL between the East 1/4 corner and the center of Section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                           |                          |                          |
|---------------------------|--------------------------|--------------------------|
| 4. DNR Monument           | 7. DNR Monument          | 8. 1" pipe, 4" alum cap. |
| 6" Cedar, S80E, 77.1'     | 6" r.maple, S79W, 45.6'  | 5" balsam, S55W, 11.7'   |
| 7" maple, S13E, 12.3'     | 8" r.maple, N65W, 54.7'  | 8" cherry, N43W, 20.00'  |
| 5" b1.spruce, N78W, 19.0' | 3" b.cherry, N30E, 32.8' | 8" balsam, N25W, 14.3'   |
| 5" w.spruce, N53E, 32.3'  | 4" b.cherry, S70E, 52.6' | 6" cherry, N28E, 27.9'   |
- 
- 9. DNR Monument
  - 8" b.spruce, S20E, 16.4'
  - 10" hemlock, S49W, 17.3'
  - 3" cedar, N63W, 28.7'
  - 5" y.birch, N28E, 17.9'

Signed by \_\_\_\_\_ Date \_\_\_\_\_  
Surveyor's Michigan License No. RLS 21558