

OK B.M.C.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette  
(County)

Located In:

Corner Code =#

- 1. Public Land Survey T 46N R 23W B-1, B-2  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on 1/29, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1. N $\frac{1}{4}$  corner of Section 6. Wood post. Hemlock 14, N51E, 30 Lks.  
DO 20, N56W, 36 Lks.

B-2. Center of Section 6. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1. Found square cedar post not of record but there were three blazed trees, with "PK" nails driven in the side of each one, facing the post. Using this post the subdivision lines of Section 6 fit occupied lines very well. Replaced the square cedar post with a DNR monument.

B-2. Set at the intersection of the E-W and N-S  $\frac{1}{4}$  lines of Section 6 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1. DNR Monument.  
Face of blaze on 7" bl.cherry, N50W, 19.8'  
P.K. nail { 5" bl.cherry, S22W, 7.6'  
in the { 8" maple, S76E, 9.4'  
side of { 11" maple, N31E, 11.2'

B-2. DNR Monument.  
4" spruce, S84W, 48.5'  
5" spruce, N78W, 20.9'  
7" maple, N18E, 23.8'  
9" spruce, S67E, 43.5'

Signed by \_\_\_\_\_ Date \_\_\_\_\_

Surveyor's Michigan License No. RLS 21558