

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-370
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 24W	M-13
	T 47N R 23W	A-13
	T 46N R 24W	M-1
	T 46N R 23W	A-1 ✓
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 29 AM 10:40
RECEIVED FOR RECORD
MARQUETTE COUNTY
MICHIGAN
REGISTER OF DEEDS
Liber 1 PAGE 66
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13: Section Corner common to Section 36, T47N-R24W; Section 31, T47N-R23W; Section 6, T46N-R23W; and Section 1, T46N-R24W. 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
14" Birch N50E, 47 l
30" Hemlock S45W, 35 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8" iron with RLS cap 17618 apparently set in 1974. DNR surveyor Paul Bresette apparently used this corner in the setting of the East 1/4 corner of Section 36, T47N-R24W. His corner record indicates the 1/4 corner as set halfway and on line between the Section Corners. He indicates a stream call North of the 1/4 corner as checking with 1 foot and stream call to East also checks well. Donnan distances to the South indicate the correct proportioned distances using this corner for a survey in the South 1/2 of the NE 1/4 of Section 1, T46N-R24W. Replaced 5/8" iron with Marquette County Survey Monument. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
7" Maple N07E 5.27 ft.
6" Maple S37E 13.46 ft.
7" Maple S27W 17.74 ft.
4" Maple N63W 16.21 ft.
Monument is 0.40 ft. above ground.
Bk. 4, Pg. 81



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589