

**SURVEY &  
REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 29 PM 1:56

*Robert A. Menley*  
REGISTER OF DEEDS

For corners in

Marquette

(County)

Located In:

Corner Code =#

- |                                    |   |     |   |     |        |
|------------------------------------|---|-----|---|-----|--------|
| 1. Public Land Survey              | T | 46N | R | 25W | M-12   |
|                                    | T | 46N | R | 24W | A-12 ✓ |
|                                    | T |     | R |     |        |
|                                    | T |     | R |     |        |
| 2. Property Controlling In Section | S |     | T | R   |        |
|                                    | S |     | T | R   |        |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |        |
|                                    | S |     | T | R   |        |

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**

*Larry J. Beasom*  
DATE Sept 26 1994

LIBER 1 PAGE 234  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Michael Mileski, September 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-12; East One-Quarter Corner Section 36;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12; East One-quarter Corner Section 36;

Corner is now located in a flooded area. Found no evidence of U.S. or M.C.R.C. monumentation or accessories. Reestablished the east one-quarter corner of section 36 midway and on line between the southeast corner of section 36 and the northeast corner of section 36.

State Plane Coordinates  
For E $\frac{1}{4}$  Cor. 36-46-25  
Grid System - NAD 83  
Zone Number - 2111 Michigan North  
Units - International Feet  
Y = 567909.54242  
X = 26154302.57443

State Plane Coordinates  
For Witness Corner  
Grid System - NAD 83  
Zone Number - 2111 Michigan North  
Units - International Feet  
Y = 568226.47703  
X = 26154305.87655

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12; East One-quarter Corner Section 36;

See back of form.



Signed by *Michael Mileski*

Date 21 Nov 1994

Surveyor's Michigan License No. 39091