

**SURVEY &  
REMONUMENTATION**

1993

**COMMISSION**

JOB NUMBER: 93300  
SHEET NO. : 1-422  
For corners in

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>24W</u>	<u>R-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1993 DEC 29 AM 10:36  
*Johnnie E. H. ...*  
REGISTERED SURVEYOR  
LIBER 1 PAGE 31  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Saturday, December 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B-1: North Quarter Corner Section 6. Not part of original 1980 - G. Carlson set a 5/8" iron with RLS cap proportionately on line on West edge of North/South dirt road referenced by:  
 12" Maple S20W 13.17 ft.  
 5" Maple West 8.62 ft.  
 13" Maple N54W 6.73 ft.  
 6" White Birch N86E 27.62 ft.  
 15.51 ft. West of the South Quarter Corner of Section 31, T47N-R24W. L4 RC, Pg. 23

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 - The 1993 remonumentation survey discovered an error in calculations in the 1980 position calculated by G. Carlson. The correct position was calculated proportionately on line between the NW and NE corners of Section 1, 30.98 ft. West of the South 1/4 corner of Section 31. Set a Marquette County Survey Monument. Peer group ratification 12-6-93.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
 12" Maple N43E 9.11 ft.  
 12" Maple S36E 9.29 ft.  
 6" Maple S57W 16.50 ft.  
 7" Maple N41W 10.90 ft.  
 Monument is flush with ground.  
 Bk. 2, Pg. 114



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589