

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-421
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
RECEIVED FOR RECORD
1993 DEC 29 AM 10:36
REGISTER OF DEEDS
JFB

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 24W	C-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 1 PAGE 32
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Saturday, December 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1: Section Corner common to Sections 5 & 6, T46N-R24W.	1980 - G. Carlson set 5/8" iron with RLS cap proportionately
1845: William Ives's original notes describe the corner	on line on East slope referenced by:
as a wood post 47 l West of the Section Corner common to	15" Oak N14E 26.76 ft.
Sections 31 & 32, T47N-R24W referenced by:	8" Maple N76E 8.67 ft.
14" Maple S61E, 07 l	11" Maple S12E 13.47 ft.
5" Fir S41W, 17 l	7" Maple S54W 11.04 ft.
	31.02 ft. West of the SW corner of Section 32, T47N-R24W.
	L4 RC, Pg. 23

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8" iron with RLS cap 24589 as described in G. Carlson witnessess 1980. Replaced with Marquette County Survey Monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
10" Maple N34E 48.48 ft.
10" Maple N77E 8.64 ft. Carlson NBT
11" Maple S13E 13.49 ft. Carlson NBT
10" Maple S54W 11.06 ft. Carlson NBT
Monument is 0.1 ft. above ground and falls on a hillside.
Ek. 2, Pg. 116



Signed by Gerald W. Carlson

Date 12-28-93

Surveyor's Michigan License No. 24589