

RF

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1999 DEC 22 AM 11: 22

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
MARQUETTE  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 46N R 24W C-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Patricia A. Monley*  
REGISTER OF DEEDS

LIBER **R2** PAGE **180**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on September 29, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9: Section Corner common to Sections 19, 20, 29, and 30, T46N-R24W  
1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:  
14" Sugar S21W, 24 L 17" Sugar N35E, 35 L

(SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9: 1997: No original corner evidence found. Found and rejected a 1/2" Steel Rod with unidentifiable cap, lying horizontal, 1.5' below ground. The corner was reset on line by double proportionate measurement between the Northeast corner of section 6 and the Southeast corner of section 30 and the Northwest corner of section 30 and the Northeast corner of section 29. Distance North is 20,989.66', South is 5251.09', East is 5322.61' and West is 5087.60'.  
Line Calls Checked: A stream line call of 68.5 chains East checked within 15'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9: 1997: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is flush with the ground.

Established new references:

16" Maple S67W, 47.24' 4" Maple S40E, 13.80'  
5" Maple S75E, 33.85" 12" Maple N65E, 37.05'

Green Steel Sign Post w/ Yellow Survey Marker Sign S56E, 3.7'

Note: New bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.  
T46N-R24W Bk. 13, Pages 7-10

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry Busorn*  
DATE 9/13/99



Signed by Gerald W. Carlson

Date 12-8-99

Surveyor's Michigan License No. 24589

PART A CONTINUED:

1964: A Government Monument Witness Record by C.C. Lindgren, P.S. (Michigan State Highway Department), indicates the corner as a found 4" Square Maple Post. Distance S02-10'-52"W, 5188.66' to the S.E. Corner of Section 30. Referenced by:

6" Maple	S40W,	18.73'	5" Maple	N10W,	18.69'
4" Maple	N80E,	10.06'			

1964: Michigan State Highway Department plans for State Project #52996CCI, Sheet No. 8, indicates the corner as a found 4" Square Maple Post. Referenced by:

6" Maple	S40W,	18.73'	5" Maple	N10W,	18.69'
4" Maple	N80E,	10.06'			

1978: An LCRC recorded by William F. Robey, P.S. #20711, in L. 1, RC Pg. 218, indicates that he found no original witnesses, but that he found a wooden stake. Checked distance to stream to East with original notes and distance checked good. He set a 1/2" X 24" Steel Rod referenced by P.K. nails in:

16" Maple	S85W,	20.70' (N. Root) (Sec. Cor. Tag on tree)
8" Maple	S14W,	9.47' (W. Root)
8" Maple	N40E,	3.94' (W. Root)

SECTION