

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-419
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
<u>MARQUETTE</u> (County)		
1. Public Land Survey	T <u>46N</u> R <u>24W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
MARQUETTE COUNTY
MICHIGAN
1993 DEC 29 AM 10:36
REGISTER OF DEEDS

LIBER 1 PAGE 34
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: Section Corner common to Sections 4 & 5, T46N-R24W. 1980 - G. Carlson set a 5/8" iron with RLS cap proportionately on line on West slope on East/West
 1845: William Ives's original notes describe the corner blaze line. Referenced by:
 as a wood post 33 1 West of the corner to Section 32 & 33, T47N-R24W referenced by:
 8" Yellow Birch S27E 11.10 ft.
 9" Sugar S36E, 29 1 10" Maple S42W 13.64 ft.
 7" Hemlock S50W, 32 1 6" Maple N30W 5.67 ft.
 7" Maple N25E 18.41 ft.
 21.78 ft. West with SE corner of Section 32, T47N-R24W.
 L4 RC, Pg. 23

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5" iron with RLS cap 24589 as described in the 1980 G. Carlson witness. Accepted this monument as the corner and replaced it with a Marquette County Survey Monument. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 11" Maple S44W 13.69 ft. Carlson NBT
 8" Maple N25W 5.66 ft. Carlson NBT
 8" Maple N27E 18.36 ft. Carlson NBT
 8" Maple S55E 6.38 ft.
 Monument is 0.40 ft. above ground.
 A very old fence travels South from this corner position.
 Bk. 4, Pg. 69



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589