

1993

CERTIFICATE

JOB NUMBER: 93300
SHEET NO. : 1-418
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 29 AM 10:36
Gerald W. Carlson
REGISTER OF DEEDS

MARQUETTE (County)		Located In:	Corner Code #
1. Public Land Survey	T46N R24W	F-1	
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

LIBER 1 PAGE 35
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Wednesday, December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1: North Quarter Corner Section 4. Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Set the corner proportional distance between the Northeast and Northwest corners of Section 4 on line between the South 1/4 corner and the Southwest corner of Section 33, T47N-R24W. 16.33 ft. West of the South 1/4 corner of Section 33, T47N-R24W. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 7" Maple N11W 13.66 ft.
 - 19" Maple N78E 18.33 ft.
 - 4" Maple S25E 22.84 ft.
 - 5" Maple S53W 14.69 ft.
- Bk. 4, Pg. 65



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589