

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-417
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE (County) Located In: Corner Code #

1. Public Land Survey	T 46N R 24W	G-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

2003 DEC 29 AM 10:36

REGISTER OF DEEDS

Gerald W. Carlson

LIBER 1 PAGE 36
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on wednesday, December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1: Section Corner common to Section 3 & 4, T46N-R24W. 1980 - G. Carlson found a 1/2" iron with RLS cap #20711 on 1845; William Ives's original notes call for a wood post the Easterly slope referenced by:
43 1 West of the corner to Sections 33 & 34, 6" Maple S01W 16.75 ft.
T47N-R24W referenced by: 7" Maple S72E 8.81 ft.
6" Birch S63W, 37 1 7" Maple N48E 12.60 ft.
18" Birch S25E, 36 1 5" Maple S05W 11.39 ft.
29.25 ft. West of Southeast corner of Section 33, T47N-R24W.
LA RC, Pg. 23

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 1/2" iron with RLS cap #20711 28.22 ft. West of the Section corner common to Sections 33 & 43, T47N-R24W. Accepted this found iron as the corner. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
7" Maple S66E 8.78 ft. Carlson NBT
6" Maple S10W 16.87 ft. Carlson NBT
5" Maple N88W 11.44 ft. Carlson NBT
7" Maple N55E 12.55 ft. Carlson NBT
Monument is 0.3 ft. above ground.
Bk. 4, Pg. 61



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589