

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 0-416
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: MARQUETTE (County) Corner Code # _____

1. Public Land Survey	T <u>46N</u> R <u>24W</u>	H-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 37
Register of Deeds Stamp & File Number

RECEIVED FOR RECORD
MARQUETTE COUNTY MICHIGAN
DEC 29 AM 10:37
1993

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, GERALD W. CARLSON, in a field survey on Thursday, December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1: North Quarter Corner Section 3. Not part of the original survey. 1993: Glenn Van Neste found a 1" pipe 5.5 ft. tall 17.5 ft. South of edge of field 1.5 ft. West of North/South and East/West fences referenced by:
6" Maple AZ. 206 9.80 ft.
8" Hemlock AZ. 94 14.28 ft.
Fence corner AZ. 93 1.50 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 3/4" pipe referenced to in the Van Neste survey. A East/West fence running South from this corner was also found. Distance between corresponding Section Corners East and West fits within 5 ft. of the split between the corresponding corners East and West. Accepted this iron as the North 1/4 corner of Section 3. Replaced with a Marquette County Survey Monument. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
8" Hemlock N89E 24.70 ft.
7" Hemlock S72E 23.36 ft.
6" Maple S24W 9.53 ft. Van Neste NBT
11" Hemlock N78W 3.00 ft.
Monument is 0.4 ft. above ground.
Bk.4, Pg. 18



Signed by Gerald W. Carlson

Date 12-28-93

Surveyor's Michigan License No. 24589