

SURVEYOR  
RECORDS

1993

COMMISSION

JOB NUMBER: 93300  
SHEET NO. : 1-415  
For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

_____ (County)	Located In:	Corner Code #:
1. Public Land Survey	T <sub>46N</sub> R <sub>24W</sub>	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

HARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1993 DEC 29 AM 10:37  
REGISTER OF CLERKS  
LIBER 1 PAGE 38  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Thursday, December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-1: Section Corner common to Sections 2 & 3, T<sub>46N</sub>-R<sub>24W</sub>.  
1845: William Ive's original survey notes described the corner as 25 l West of the Section Corner common to Sections 34 & 35, T<sub>47N</sub>-R<sub>24W</sub> referenced by:  
10" Hemlock S71E, 13 l  
10" Hemlock S75W, 21 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found a 5/8" iron 16.37 ft. West of the Section Corner common to Sections 34 & 35, T<sub>47N</sub>-R<sub>24W</sub>. On the Westerly edge of County Road 545. The G.L.O. offset this listed at 16.50 ft. at this corner. Distances to corresponding corners East and West checked well. Accepted this corner position for the corner and set a Marquette County Survey Monument. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 5/8" rebar with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
4" White Pine S88E 45.65 ft.  
15" Maple S40E 85.24 ft.  
4" White Pine S50W 37.23 ft.  
5" White Pine N77W 31.62 ft.  
Monument is 0.50 ft. below grade.  
Bk. 4, Pg. 14



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589