

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300
SHEET NO. : 1-414
For corners in

MARQUETTE COUNTY
RECEIVED FOR RECORD
093 DEC 29 AM 10:37
REGISTER OF DEEDS

Located in: _____ Corner Code: # _____

1. Public Land Survey T 46N R 24W J-1 _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER 1 PAGE 39
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Thursday, December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1: North Quarter Corner Section 2. Not part of original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 1/2" iron rebar and cap LS #20711. The distance between the NW corner of Section 2 and the NE corner of Section 2 to this found rebar checks within 0.05 ft. of the split between the corners. Accepted this iron as the corner. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
9" Maple N33E 13.69 ft.
12" Maple N68E 36.63 ft.
5" Hemlock S70E 18.25 ft.
14" Maple N28W 9.21 ft.
Monument is 0.4 ft. above ground.
Bk 4, Pg. 22



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589