

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300
 SHEET NO. : 1-413
 For corners in:

Located In:	Corner Code #
MARQUETTE (County)	
1. Public Land Survey	T _{46N} R _{24W} K-1
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

LIBER 1 PAGE 40
 Register of Deeds Stamp & File Number

RECEIVED FOR RECORD
 MARQUETTE COUNTY MICHIGAN
 1993 DEC 29 AM 10:37
 REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1: Section Corner common to Section 1 & 2, T46N-R24W.
 1845: William Ive's original survey notes described the corner as a wood post 12 1 West of corner to Sections 35 & 36 T47N-R24W referenced by:
 22" Hemlock S58E, 24 1
 12" Hemlock S45W, 24 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - No evidence of original bearing trees was found. A 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument was set at 7.92 ft. West of the Section Corner common to Sections 35 & 36, T47N-R24W on line with the SE and South 1/4 corners of Section 35, T47N-R24W.
 Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 6" Spruce N67E 223.97 ft.
 6" Maple S38E 191.81 ft.
 17" Spruce S44W 103.12 ft.
 6" Poplar N66W 136.62 ft.
 Corner is 145 ft. SW of the US-41 & KUNDE Rd. intersection.
 Bk. 4, Pg. 73.



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589