

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-412
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

_____ MARQUETTE _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 24W	L-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY
 RECEIVED FOR RECORD
 MICHIGAN
 1993 DEC 29 AM 10:37
 REGISTER OF DEEDS
 1 PAGE 41
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1: North Quarter Corner Section 1. Not part of original survey. 1978: W. Donnan recorded a found 3 1/4" iron rod referenced by:
 10" Maple N59E 11.19 ft.
 6" Maple S78W 17.28 ft.
 6" White Birch S02E 10.45 ft.
 L1 RC, Pg. 229

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Research conducted in the 1993 remonumentation survey indicates that W. Donnan referenced this corner common to Section 36, T47N-R24W which is incorrect because of the double corner at the NW corner of Section 1, T46N-R24W. The corner position was calculated by proportional distance on line between the NE corner and NW corner of Section 1, T46N-R24W and on line between the South 1/4 corner on the SW corner of section 36, T47N-R24W. Set a Marquette County Survey Monument at this corner position 3.54 ft. West of the South 1/4 corner Section 36, T47N-R24W. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 13" Maple N69E 14.31 ft.
 7" Maple S78E 20.56 ft.
 9" White Birch S15E 11.30 ft.
 9" Maple S89W 10.53 ft.
 Monument is 0.2 ft. above ground.
 Bk. 4, Pg. 77



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589