

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46. NR. 25. W.

----- Marquette -----

----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 4, 5, 8, 9 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 8" J. Pine - S 70 E - 138 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Burned over plains, no original evidence remaining. A 1" Iron Pin has been placed at the intersection of fire lanes, approximately 65' North of corner, erroneously, I believe.

Corner was placed and witnessed September 5, 1951.

SURVEYORS SEAL

SIGNED Sam C. DeLoater
REGISTERED LAND SURVEYOR

DATE 11/1/51